



Irrigation System Service Program

Bronze	Silver	Gold	Platinum	Included Service
✓	✓	✓	✓	COMPREHENSIVE SPRING STARTUP: Turn on main ball valve, install backflow preventer, pressurize system, and check backflow preventer for leaks. Run test on each zone to check for possible leaks, proper operation, and head adjustment. Check rain sensor. Program controller for proper seasonal conditions.
✓	✓	✓	✓	WINTERIZATION: Turn off water at main ball valve, remove backflow preventer if needed. Using air compressor remove water from above- and below ground pipes, for each sprinkler zone.
			✓	MAY: Comprehensive Service Visit: Run test on each zone to check for possible leaks, proper operation, and head adjustment. Check rain sensor. Program controller for proper seasonal conditions.
		✓	✓	JUNE: Comprehensive Service Visit: Run test on each zone to check for possible leaks, proper operation, and head adjustment. Check rain sensor. Program controller for proper seasonal conditions.
	✓		✓	JULY: Comprehensive Service Visit: Run test on each zone to check for possible leaks, proper operation, and head adjustment. Check rain sensor. Program controller for proper seasonal conditions.
		✓	✓	AUGUST: Comprehensive Service Visit: Run test on each zone to check for possible leaks, proper operation, and head adjustment. Check rain sensor. Program controller for proper seasonal conditions.
			✓	SEPTEMBER: Comprehensive Service Visit: Run test on each zone to check for possible leaks, proper operation, and head adjustment. Check rain sensor. Program controller for proper seasonal conditions.

Call or e-mail to learn more about availability and pricing